UNIVERSITY OF CALICUT
ENGINEERING DEPARTMENT, ELECTRICAL WING

No. 195189/ENG. ED-DRAUGHTSMAN-1 (EL)/2026/Admn Dated, **03.11.2026**

QUOTATION NOTICE

Sealed competitive quotations in the prescribed form and superscribed by the name of works are invited from Registered Contractors, possessing Electrical contract License of appropriate grade issued by Kerala State Electricity Licensing Board for the following works so as to reach the office of the undersigned on or before **3 PM on 11.11.2026**. The quotations will be opened at 3.30 PM on the same day. **(11.11.2026).**

Sl. No.	Name of Work	PAC (Rs.)	Time of completion
1	**Additional electrification in connection with eco proof ceiling on class No.220 & 221 in the Department of Sanskrit under PM USHA Scheme**	**Rs. 16,051/- + 18% GST**	**10 days**

The quotation schedule can be had from the office of the Executive Engineer (Ele) on all working days from **03.11.2026 to 1 PM on 11.11.2026**. The Executive Engineer (Ele), Engineering Department, Calicut University reserves the right to reject the lowest or any quotation without assigning any reason thereof. Responsibility for getting scheme approval and safety certificate from the Electrical Inspector/Submission of necessary drawings, duly filled application forms etc. to get Electrical Service Connection in KSEB lies on the Contractor.

OFFICE OF THE EXECUTIVE ENGINEER (ELEC.) CALICUT UNIVERSITY P.O. PIN: 673 635 Date:..... UNIVERSITY OF CALICUT

EXECUTIVE ENGINEER (ELECTRICAL)
Executive Engineer (Elec.)
University Engineering Dept.
Calicut University .P.O. 673 635

Office of the Executive Engineer (Electrical),
University of Calicut
Ph: 0494-2407306
0494-2407308

UNIVERSITY OF CALICUT
(Engineering Department, Electrical wing)

PAC : Rs.16,051/- +18% GST
SD :5% of the quoted amount
Time of Completion: 10 days

No. 195189/ENG. ED-DRAUGHTSMAN-1 (EL)/2026/Admn

QUOTATION SCHEDULE

Name of Work: Additional electrification in connection with eco proof ceiling on class No.220 & 221 in the Department of Sanskrit under PM USHA Scheme.

Sl. No.	Qty	Particulars	Rate	Unit	amount
1	5	1.14.1 Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2x1.5 sq.mm + 1x1.5 sq.mm earth wire	246.52 (Rupees two hundred forty six and paise fifty two only)	metre	1,232.60
2	14	1.14.2 Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	291.09 (Rupees two hundred ninety one and paise nine only)	metre	4,075.26
3	2	1.17.3 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 X 1.5 sq.mm	100.61 (Rupees one hundred and paise sixty one only)	metre	201.22
4	4	1.17.12 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 2.5 sq. mm	145.18 (Rupees one hundred forty five and paise eighteen only)	metre	580.72
5	2	1.21.1 Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required. 20 mm	135.72 (Rupees one hundred thirty five and paise seventy two onl)	metre	271.44
6	1	1.24.3 Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.15/16 amp switch	164.80 (Rupees one hundred sixty four and paise eighty only)	each	164.80
7	1	1.24.5 Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.6 pin 15/16 amp socket outlet	208.24 (Rupees two hundred eight and paise twenty four only)	each	208.24
8	2	1.27.1 Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required.1 or 2 Module (75mmX75mm)	315.46 (Rupees three hundred fifteen and paise forty six only)	each	630.92
9	6	OD132546/2026-2027 Supplying and installation of 22-25W LED square panel recess mount light (pwd approved)	1,447.63 (Rupees one thousand four hundred forty seven and paise sixty three only)	each	8,685.78
					16,050.98
	Total	(Rupees Sixteen thousand fifty one only)			16,051.00

I/We agree to execute the above work at (x) estimate rate (xx) ..... below (xxx) ..... above the rate given in the schedule.

Contractor

EXECUTIVE ENGINEER (EL)

Executive Engineer (El
University Engineering Dep
Calicut University .P.O. 673 6