UNIVERSITY OF CALICUT
ENGINEERING DEPARTMENT, ELECTRICAL WING

No. 195205/ENG. ED-DRAUGHTSMAN-1 (EL)/2026/Admn Dated, **03.11.2026**

QUOTATION NOTICE

Sealed competitive quotations in the prescribed form and superscribed by the name of works are invited from Registered Contractors, possessing Electrical contract License of appropriate grade issued by Kerala State Electricity Licensing Board for the following works so as to reach the office of the undersigned on or before **3 PM on 11.11.2026**. The quotations will be opened at 3.30 PM on the same day. **(11.11.2026).**

Sl. No.	Name of Work	PAC (Rs.)	Time of completion
1	**Additional electrification for providing AC in the Research hall, Seminar hall Computer Lab and Office in the Department of Sanskrit under PM USHA Scheme**	**Rs. 17,766/- + 18% GST**	**10 days**

The quotation schedule can be had from the office of the Executive Engineer (Ele) on all working days from **03.11.2026 to 1 PM on 11.11.2026**. The Executive Engineer (Ele), Engineering Department, Calicut University reserves the right to reject the lowest or any quotation without assigning any reason thereof. Responsibility for getting scheme approval and safety certificate from the Electrical Inspector/Submission of necessary drawings, duly filled application forms etc. to get Electrical Service Connection in KSEB lies on the Contractor.

OFFICE OF THE EXECUTIVE ENGINEER (ELEC.) CALICUT UNIVERSITY P.O. PIN: 673 635 Date:..... UNIVERSITY OF CALICUT

EXECUTIVE ENGINEER (ELECTRICAL)

Executive Engineer (Elec.)
University Engineering Dept.
Calicut University .P.O. 673 635

Office of the Executive Engineer (Electrical),
University of Calicut
Ph: 0494-2407306
0494-2407308

UNIVERSITY OF CALICUT
(Engineering Department, Electrical wing)

PAC : Rs.17,766/- +18% GST
SD :5% of the quoted amount
Time of Completion: 10 days

No. 195205/ENG. ED-DRAUGHTSMAN-1 (EL)/2026/Admn

QUOTATION SCHEDULE

Name of Work: Additional electrification for providing AC in the Research hall, Seminar hall Computer Lab and Office in the Department of Sanskrit under PM USHA Scheme

Sl. No.	Qty	Particulars	Rate	Unit	amount
1	24	1.14.2 Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	291.09 (Rupees two hundred ninety one and paise nine only)	metre	6,986.16
2	15	1.14.7 Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 4 X 2.5 sq. mm + 2 X 2.5 sq. mm earth wire	433.17 (Rupees four hundred and thirty three and paise seventeen only)	metre	6,497.55
3	5	1.17.12 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 x 2.5 sq. mm	145.18 (Rupees one hundred and forty five and paise eighteen only)	metre	725.90
4	4	1.21.1 Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required. 20 mm	135.72 (Rupees one hundred thirty five and paise seventy two only)	metre	542.88
5	2	2.10.1 Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, ""C"" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	270.65 (Rupees two hundred seventy and paise sixty five only)	each	541.30
6	2	2.16 Supplying and fixing DP sheet steel enclosure on surface/ recess along with 25/32amps 240 volts "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	1,236.31 (Rupees one thousand two hundred thirty six and paise thirty one only)	each	2,472.62
					17,766.41
	Total	(Rupees Seventeen thousand seven hundred and sixty six only)			17,766.00

I/We agree to execute the above work at (x) estimate rate (xx) ..... below (xxx) ..... above the rate given in the schedule.

Contractor

EXECUTIVE ENGINEER (EL)

Executive Engineer (Elec.)
University Engineering Dept.
Calicut University .P.O. 673 635